

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas**

WELL PLUGGING RECORD

Barton County. Sec. 1 Twp. 20 Rge. (E) 14 (W)

Location as "NE/CNW¼SW¼" or footage from lines CEL NE SW

Lease Owner E. H. Adair

Lease Name Merten Well No. 1

Office Address 407 W-K-H Building. Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 7 19 51

Application for plugging filed December ~~November~~ 2 19 51

Application for plugging approved December 2 19 51

Plugging commenced December 7 19 51

Plugging completed December 7 19 51

Reason for abandonment of well or producing formation Barren

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Set.
Filled with mud to 250' put in 15' of rock bridge and
dumped 15 sx cement, filled with mud to 30' of surface
dumped 10 sx cement, filled to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... E. H. Adair Oil Company
Address..... Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

STATE OF _____, COUNTY OF _____, ss:
RUSSELL L. BAKER (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
 described well as filed and that the same are true and correct. So help me God.

(Signature)

Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 29th day of December, 1951

My commission expires September 15, 1953

23-5091-s

8-50—10M

Notary Public.

PLUGGING
FILE SEC 1 I 202 160
BOOK PAGE 30 LINE 21

JLN - 2

1-2-52

E. H. ADAIR OIL COMPANY

Merten

No. 1

3499' TD

Comn. 10/28/51 Comp. 11/7/51

781' 8 5/8" s/csg, 350sx cement
3499' 5 1/2" csg, 100~~ex~~cement

15.009.01674.00.00
Sec. 1, T. 20 R 14 W

CEL NE SW

~~Section 14~~ County, Kansas
Barton

Elevation 1871 DF
1873 KB

Sand	0-80
Shale & Shells	80-175
Shale	175-280
Sand	280-315
Shale & Sand	315-725
Shale Red	725-778
Anhydrite	778-810
Shale	810-1700
Shale & Shells	1700-1775
Lime	1775-1885
Lime & Shale	1885-2113
Shale & Shells	2113-2316
Shale	2316-2493
Shale & Shells	2493-2857
Lime & Shale	2857-2921
Lime	2921-3140
Shale	3140-3209
Lime	3209-3212
Lime Brown	3212-3224
Lime	3224-3457
Conglomerate	3457-3496
Lime	3496-3499 Rotary

Certified Correct

Ed Baker

PLUGGING

FILE SEC-1 T-20 R-14W

BOOK PAGE 130 LINE 21