


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 6 Twp. 17 Rge. 14W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE NW SE  
Lease Owner Murfin Drilling Co.  
Lease Name Janke Well No. 1  
Office Address Union Center Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 13 19 59  
Application for plugging filed October 12 19 59  
Application for plugging approved October 12 19 59  
Plugging commenced October 12 19 59  
Plugging completed October 13 19 59  
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3537 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	833.94'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Filled hole with heavy mud to 400'. Set plug. Put in 35 sacks cement and 1/2 sack hulls. Filled to 40'. Set plug. Put in 1/2 sack hulls and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor C-G Drilling Co.  
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) G. F. Galloway  
107 Rule Building  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 19 59  
My commission expires May 20, 1963  
Vicky Jacobs  
Vicky Jacobs Notary Public.



W E L L L O G

OPERATOR Murfin Drilling Co.

SEC. 6-17-14W

WELL NAME Janke #1

LOC. SE NW SE

TOTAL DEPTH 3537'

COUNTY Barton

COMM. September 30, 1959 COMP. October 13, 1959

STATE Kansas

RIG NO. 2

ELEVATION 1977' R.B.

CASING: Ran 833.94' (27 jts.) 8-5/8" OD Surface Casing.

PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	310	Shale-Sand		
310	455	Sand		
455	615	Shale-Sand		
615	970	Red Bed		
970	1012	Anhydrite		
1012	1715	Shale-Shell		
1715	1975	Shale-Lime		
1975	2902	Lime-Shale	0° - 2500	
2902	3066	Lime	0° - 2750	
3066	3106	Lime-Shale	0° - 3000	
3106	3168	Lime		
3168	3537	Lime	0° - 3250	DST 3454-3482'

RECEIVED  
STATE CORPORATION COMMISSION

OCT 21 1959

STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By *G. F. Galloway*  
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 19th day of October, 1959.

My commission expires:  
May 20, 1963

*Vicky Jacobs*  
Vicky Jacobs - Notary public

