


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above Section Flat

Barton County, Sec. 2 Twp. 17S Rge. (E) 14 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$  SW $\frac{1}{4}$  NW $\frac{1}{4}$   
Lease Owner Iron Drilling Company  
Lease Name Kingston Well No. 1  
Office Address 1206 Philtower Building, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 12, 19 52  
Application for plugging filed February 12 19 52  
Application for plugging approved February 12 19 52  
Plugging commenced February 12 19 52  
Plugging completed February 12 19 52  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Dry Hole Depth to top Bottom Total Depth of Well 3475' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	274'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud.  
Wood plug set at 270' and cemented with 15 sax.  
Wood plug set at 35' and cemented with 10 sax.

4-12-52

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to Iron Drilling Company  
Address 1206 Philtower Building Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
Herrick Babcock (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herrick Babcock  
1206 Philtower Building, Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of February, 19 52

My commission expires Feb. 28, 1952 B. Michael Notary Public.



15.009.00067.00.00

DRILLING RECORD

Well No. 1 Kingston  
SE SW NW Sec. 2-178-14W  
Barton County, Kansas

Casing Record

274' of 8-5/8" OD Surface Pipe  
cemented with 175 sacks.

Work Commenced 1/29/52  
Drilling Commenced 1/31/52  
Drilling Completed 2/12/52  
Work Completed 2/13/52

No Oil String - Dry Hole

WELL LOG

Shale & Sand	0 to 20
Sand	20 to 40
Shale	40 to 505
Sand	505 to 575
Shale & Shells	575 to 625
Sand & Shale	625 to 655
Shale & Shells	655 to 715
Red Bed & Shale	715 to 953
Anhydrite	953 to 983
Shale & Shells	983 to 1660
Broken Lime	1660 to 1735
Lime & Shale	1735 to 1960
Lime	1960 to 2085
Broken Lime	2085 to 2195
Shale & Shells	2195 to 2215
Shale & Lime	2215 to 2340
Lime	2340 to 2465
Shale & Shells	2465 to 2770
Shale	2770 to 2790
Lime	2790 to 2860
Shale & Lime	2860 to 2904
Lime (Topeka)	2904 to 2950
Lime	2950 to 3155
Shale	3155 to 3210
Lime	3210 to 3425
Conglomerate	3425 to 3455
Lime	3455 to 3465
Arbuckle	3465 to 3475 TD

CERTIFICATION

State of Oklahoma, County of Tulsa, SS

I, Herrick Babcock, Partner of Iron Drilling Company, Certify that the above is a true and correct log of the above described well.

**PLUGGING**  
 FILE SEC. 2-178-14W  
 BOOK PAGE 144 LINE 16  
 Subscribed to and sworn before me this 18th day of February, 1952.

*Herrick Babcock*

*B. Michal*

Notary Public

My commission expires Feb. 28, 1952