

State of Kansas



15.159-00355-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1967

CONSERVATION DIVISION
Wichita, Kansas

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 4, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Tomlinson-Kathol, Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Lackey Estate Well No. 1

Location: NW NW NE Sec. 1 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3385' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Push 5 1/2" plug to 3320'. Fill hole with sand to 3310' and cement with

5 sacks. Fill hole with mud to 210'. Set rock bridge from 210' to

200' and cement hole with 25 sacks. Fill hole with mud to 40'.

Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

William J. Lomen
Conservation Division Agent