



15-009-07251-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1965
07-22-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Weber Well No. # 3

Location: SE NE NW Sec. 13 Twp. 16 Rge. 12 (E)(W) W

County Barton Total Depth 3313 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Watson was instructed to plug the well as follows:

8 5/8" 240' Cwc.

Set bottom plug @ 2900' & 5 sax cement with dump bailer.

Pulled pipe. Mud to 240'; set rock bridge; displaced 25 sax cement. Mud to 40'; set rock bridge & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent