



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

May 15, 1964

RECEIVED  
STATE CORPORATION COMMISSION

MAY 21 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Elmo Finch of Pipe Pullers Inc. has this

date requested permission to plug the following described well:

Mr. Finch guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr.

Complete Address: 4722 Broadway, Kansas City, Missouri

Lease Name: McClintock Well No. 1

Location: NE NE NE Sec. 18 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3510' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Finch was instructed to plug the well as follows:

Push 4 1/2" plug to 3275'. Fill hole with sand to 3265' and  
cement with 3 sacks. Fill hole with mud to 220'. Set  
rock bridge from 220' to 210' and cement hole with 10 sacks.  
Fill hole with mud to 40'. Set rock bridge from 40' to  
30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent