



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water) 1
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 29, 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1964

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bill Neal of Triple "D" Drilling Co. has this date requested permission to plug the following described well:

Mr. Neal guarantees payment of the plugging fee.

Operator's full Name: Northeastern Petroleum Co.

Complete Address: 2400 N. Main, Hutchinson, Kansas

Lease Name: Keely Estate Well No. 2

Location: SE NW SE Sec. 30 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3395' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Neal was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/2 sack hulls to 200' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent