

15-009-07256-0000
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 58-22

LOCATION NW-SE-NW

SEC. 13 TWP. 16 RGE. 12w

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 4 Lease Weber

Operator Morton Specter Address Russell Kans.

Field County Barton

Total Depth 3325 Feet.

Plugging Contractor Rd S. Pipe Pulling Co.

Plugging Contractor's License No. 1.

Address Ellinwood Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 1/2" @ 779' c.w.c. Oil string 5 1/2"
set 3325' w/ 200 st Cem. Top perf 3057'
Sanded hole to 3040' dumped 5 st Cem.
Shot off and pulled 5 1/2" casing. Mudded hole
to 250' set rock bridge, run 20 st Cem
mud to 35' rock bridge and 10 st Cem
to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

09-21-54

Warren H. Garner
District Conservation Agent

Date Sept 17, 1954

PLUGGING
FILE SEC 13 16 R/20
BOOK PAGE 58 LINE 22