

15-009-15755-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 101-43

LOCATION SE 1/4 - NENE SE

SEC. 13 TWP. 16 RGE. 12-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease A. Hoffmann

Operator Walt Co. of Refinery, Paris Address 820 W. N. Bk. Bldg. Wichita Kans.

Field _____ County Barton

Total Depth 2309 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4" - 710 ft. Not cemented - 5 1/2" casing set at
1330 ft. - 35 sacks of cement. Dumped 10 sacks of cement
on bottom of hole. Shot off & pulled the 5 1/2" casing - mud to
715 ft. Set back bridge & 20 sacks of cement at 715 ft. mud to
330 ft. Set back bridge & 25 sacks of cement at 330 ft. -
mud to 30 ft. bridge & 10 sacks of cement at the
surface - pulled all of the 10 3/4" casing -

Walt Supply Co. - Plugging **RECEIVED**
STATE CORPORATION COMMISSION

AUG 25 1951

08-25-51 CONSERVATION DIVISION

Wichita, Kansas

C. M. Stoeckli
District Conservation Agent

Date 8-23-51

PLUGGING
FILE 101-43-16-11W
BOOK 101-43