

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1959

CONSERVATION DIVISION
Wichita, Kansas

R
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Barton

Location: NE SE SE Sec. 13 Twp. 16 Rge. 12W (E) (W)

Name of Field: _____ Total Depth: 3322

I have this date completed supervision of plugging of:

Lease Name: Hoffman Well No. # 5

Operator's Full Name: Morgenstern & Specter Inc.

Complete Address: Russell, Kansas

Plugging Contractor: E & L Casing Pulling Co.

Address: 1003 Heiser, Great bend, Kansas License No. # 249

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour _____ Day 6 Month 11 Year 1959

The above well was plugged as follows:

Sand back to 3300' & 5 sax cement with dump bailer. Pulled pipe.
Pumped 20 sax mud in hole @ 2900'. Pulled pipe to 440' & circulated mud.
Pulled pipe; run 2" tubing to 340'; pumped 15 sax mud & 50 sax cement
with pump truck. Mud to 30' set rock bridge, & 25 sax cement, cementing
to base of cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 1/12/60
INV. NO. 407-w