

KANSAS

Form CP-3  
Rev. 6-26-62

*JP*  
STATE CORPORATION COMMISSION 15-009-03304-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

AUG 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Woodman-Iannitti Drlg. Co.

Complete Address: 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name Dolechek Well No. 4

Location C N/2 SE SW Sec.      Twp. 13 Rge. 16 (E) 12(W) X

County Barton Total Depth 3153

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 10 A Day 12 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 3153' 13" csg set at 349' cwc 300 sx

7" csg set at 3087' cw 100 sx cmt.

7" csg FBTDs 3025' without top perf. at 2870'.

Filled 7" csg with sand (2850-3025) and dumped 6 sc cmt with dump bailer. (2850-10)

Cutoff and recov. 700' of 7" csg.

Pumped down 13" csg with 15 sx gel (450-700) 50 sx cmt (300-450) 10 sx gel (40-300)

and 20 sx cmt (0-40)

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Wauson  
Well Plugging Supervisor

INVOICED

DATE 8/14/68  
INV. NO. 8284-W