

KANSAS



STATE CORPORATION COMMISSION

15-009-03303-0000

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

AUG 14 1968

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Woodman-Iannitti Drlg. Co.

Complete Address: 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name Dolechek Well No. 3

Location C N/2 SW SW Sec. 13 Twp. 16 Rge. 12 (E) (W) X

County Barton Total Depth 3329

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 9 A Day 12 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 3329' 13" set at 355' cwc.

5 1/2 csg set at 3320' cw 100 sx cmt.

Pushed plug to 2650' and dumped 5 sx cmt with dump bailer. (2610-50)

Cutoff and recov. 900' of 5 1/2 csg.

Pumped down 13 1/2" csg with 15 sx gel, 50 sx cement, 10 sx gel and 20 sx cmt.

Cmt (0-40) gel (40-300) Cmt (300-450) gel (450-900)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 8/14/68
INSR. NO. 8283-U