



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1975

CONSERVATION DIVISION
Wichita, Kansas

1-23-75

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sterling DRilling Company

Complete Address P.O. Box 129, Sterling, Kansas 67579

Lease Name Fitzpatrick "A" Well No. 1

Location NE SE SW Sec. 27 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3364'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour Noon Day 17 Month January Year 1975

The above well was plugged as follows:

Hole filled with sand to 3290' and cemented with 4 sacks cement.

Hole filled with mud to 210'. Rock bridge set from 210' to 200' and

hole cemented with 25 sacks cement. Hole filled with mud to 40'.

Rock bridge set from 40' to 30' and hole cemented to base of cellar

with 10 sacks cement.

2898' of 4 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Walter J. Somers*
Well Plugging Supervisor

DATE 1/30/75

INV. NO. 727-W