

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1975
CONSERVATION DIVISION
Wichita, Kansas
1-24-75

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sterling Drilling Company

Complete Address Box 129 Sterling, Kansas 67579

Lease Name Mathes Well No. # 1

Location C SW NE Sec. 27 Twp. 21S Rge. (E) 8(W)

County Rice Total Depth 3382'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Chase, Kansas License No. # 683

Operation Completed: Hour 2 PM Day 22 Month 1 Year 75

The above well was plugged as follows:

8 5/8"-232'-Circulated w/cement. 4 1/8"-3378'-Cemented. Top Perf. 3300'.

Top tubing in hole at 3313'. Squeezed w/25 Sax. Cement. Halliburton.

Mud to 230'. Bridge 230' to 220'. 25 Sax. Cement at 220'.

Mud to 40'. Bridge 40' to 30'. 10 Sax. Cement 30' to 0.

Pulled 2837'-4 1/8"-Pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1/30/75
INV. NO. 728-w