

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-7-81
DEC - 7

API Number 15-159-21095
CONSERVATION DIVISION
Wichita Kansas

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Dakota Resources, Inc.

Complete Address 2900 Security Life Bldg, Denver, Colorado 80202

Lease Name Wilkey Well No. 22-24

Location C SE NW Sec. 24 Twp. 21 Rge. 8 (~~East~~) (West)

County Rice Total Depth 3440'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling and Halliburton Co.

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour: 12:15 PM Day: 2 Month: December Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: PBTD - 3075' Perf 3036-38'
8 5/8" - 270 - 170 sacks 5 1/2" - 3438 - 125 sacks

Hole Filled with sand to 2950' and cemented with 5 sacks cement.
Hole squeezed with 3 sacks bulls, 20 sacks gel, and 85 sacks 50-50
permix pumped into 8 5/8" surface casing.

2929' of 5 1/2" casing recovered.

I hereby certify that the above plugging instructions were given as herein stated.
INVOICED
DATE 12-10-81
INV. NO. 8891-W
Signed: [Signature]
Conservation Division Agent