

KANSAS

Form CP-3  
Rev. 6-4-68

15-159-30482-0000

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

SEP 11 1974

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Wofford Oil Company

Complete Address 1016 Union Nat'l Bk. Bldg., Wichita, Kansas 67202

Lease Name Roscoe Coyne Well No. 1

Location NE SE Sec. 24 Twp. 21 Rge. 8 (E)      (W) X

County Rice Total Depth 3402'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Dunbar Drilling, Inc.

Address 5252 North Broadway, Wichita, Kansas License No. 709

Operation Completed: Hour 3 PM Day 4 Month September Year 1974

The above well was plugged as follows:

Hole filled with sand to 3375' and cemented with 5 sacks cement.

Hole bailed to 250'. Rock bridge set from 250' to 240'. Hole cemented with 50 sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

2743' of 5 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: *William J. Lorenz*  
Well Plugging Supervisor

INVOICED

DATE 9/11/74

INV. NO. 9868-w