



GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

June 11, 1961

RECEIVED STATE CORPORATION COMMISSION

JUN 21 1961

CONSERVATION DIVISION Wichita, Kansas

J. P. Roberts  
 Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date June 11, 1961, authorized the following plugging operation:

Operator's Full Name: Wilkinson Drilling, Inc.

Complete Address: 805 Union Center, Wichita, Kansas

Lease Name: Smisor Well No. 1

Location: NW NW SE Sec. 18 Twp. 21 Rge. 8 (E) (W) X

County: Rice Total Depth: 3572'

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 240' with heavy mud.

Push plug and 1/4 sack hulls to 240' and cement with 20 sacks thru  
drill pipe. Fill hole with mud to 35'. Push plug and 1/4 sack hulls  
to 35' and cap with 10 sacks cement.

Fill, bridge, and cement rathole with 2 sacks.

Very truly yours,

Signed: Arthur J. Tomson  
 Conservation Division Agent