

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 21 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Ben C. W. Hyde, Jr.

Complete Address: 4722 Broadway, Kansas City 12, Missouri

Lease Name McClintock Well No. 1

Location NE NE NE Sec. 18 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3510'

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 1 PM Day 18 Month May Year 1964

The Above well was plugged as follows:

4 1/2" plug pushed to 3275'. Hole filled with sand to 3265' and cemented  
with 3 sacks. Hole filled with mud to 220'. Rock bridge set from 220'  
to 210' and hole cemented with 20 sacks. Hole filled with mud to 40'.  
Rock bridge set from 40' to 30' and hole cemented to base of cellar with  
10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 5/21/64

INV. NO. 9190-W