

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

Locate well correctly on above
Section Plat

McPherson County. Sec. 20 Twp. 21 Rge. 5 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE NE
Lease Owner Hall-Prather Drilling Company
Lease Name Ediger Well No. 1
Office Address Hutchison, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 22 19 49
Application for plugging filed July 25 19 49
Application for plugging approved July 26 19 49
Plugging commenced July 22 19 49
Plugging completed July 22 19 49
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	165'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud to 150'. Set wood plug.
Run 20 sacks cement on Plug. Mud
to 10' below surface. Run 5 sacks
cement. Mud to surface

RECEIVED
AUG 4 - 1949
ST. 8-4-49

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Shawver-Graham, Inc.
Address 204 North Market
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.
(Signature) J. A. Gilliland
204 North Market, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of August, 1949.
My commission expires 1-29-53
Notary Public.

EDIGER # 1

Location: SE SE NE Commenced: 7-6-49
 Section 20-21-5W
 McPherson County, Kansas Completed: 7-21-49

Operator: Shawver-Graham, Inc.
 204 N. Market
 Wichita, Kansas

Casing Record: 165' 8 5/8 Surface
 Cemented w/ 125 Sacks


L O G

(Figures indicate bottom of formation)

Surface Soil	65	Lime	2584
Shale	75	Lime-Shale	2634
Redrock-Shells	165	Sandy-Lime	2710
Redrock-Shells	210	Lime	3065
Shale-Shells	395	Lime-Shale	3121
Shale	800	Shale-Lime	3455
Lime-Shale	990	Lime-Shale	3529
Lime-Shale	1140	Chert	3552
Shale-Shells	1210	Lime	3617
Lime	1290	Lime-Shale	3645
Lime-Shale	1490	Shale	3845
Shale-Shells	1540	Dolomite	3850
Lime-Shale	1778	Lime-Shale	3906
Shale-Shells	1900	Sandy Lime-Chert	3974
Shale	2000	Shale-Sand & Pyrite	3990
Lime-Shale	2335	Arbuckle	T.D. 4016
	<u>TOPS</u>		
Mississippi Limestone	3405	White Crystalline Viola	3903
Kinderhook Shale	3660	Simpson Shale	3927
Misener Sand	3836	Arbuckle Dolomite	4005

The undersigned, Shawver-Graham, Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHAWVER-GRAHAM, INC.

BY: 

Secretary

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BE IT REMEMBERED THAT on this 5th day of August 1949, before me the undersigned, a Notary Public, for the county and state aforesaid, came William L. Graham, Secretary of Shawver-Graham, Inc., a Kansas Corporation, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

Corporation-Div.

AUG 6 - 1949

STATE CORPORATION
 COMMISSION
 KANSAS

My Commission Expires:
 1-29-53

Notary Public

