

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County, Sec. 8 Twp. 21 Rge. (E) 5 (W)

Location as "NE/CNW/SW" or footage from lines. NW NW NW

Lease Owner Time Petroleum Company

Lease Name Petz Well No. 1

Office Address 560 N., Fourth Natl. Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-22 19 58

Application for plugging filed 2-22 19 58

Application for plugging approved 2-22 19 58

Plugging commenced 2-22 @ 9:00 A.M. 19 58

Plugging completed 2-22 @ 10:00 A.M. 19 58

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well State Pluggor

Producing formation None Depth to top Bottom Total Depth of Well 3490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with Rotary mud from 3490 to 210; Halliburton plug and 4 sacks hulls set with 15 sacks cement. Hole filled to 30' with Rotary mud. Top Halliburton plug and 1 sack hulls set with 5 sacks cement.

3-22-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Target Drilling & Producing Co., Inc.

Address 560 N., Fourth National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. R. J. Schreiner (employee of owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) R. C. Laux

560 N., Fourth Natl. Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of February, 1958

My commission expires September 19, 1959

Notary Public.



WICHITA, KANSAS  
 DRILLER'S WELL LOG

Petz #1  
 NW, NW, NW, Sec. 8-21-5W  
 McPherson County, Kansas  
 Commenced 2/11/58  
 Completed 2/22/58

Depth		Formation	Remarks
From	To		
0	170	Sand Shale Red Bed & Lime	
170	708	Shale Shells Red Bed	Hit Cement at 130'
708	900	Shale	
900	985	Lime & Shale	Made 715 Ft. in 10 Hrs.
985	1085	" "	Pulled Bit No. 2 @ 1060
1085	1285	Lime	Jetted Shale Pit @ 1235'
1285	1450	Lime Shale	
1450	1645	Shale	
1645	1805	Shale Lime	
1805	2035	Shale Lime Stks.	
2035	2250	Shale Lime Stks.	
2250	2379	Lime	
2379	2470	Lime	
2470	2554	Lime	
2554	2680	Lime Shale	
2680	2754	Lime Shale	
2754	2790	Lime, K. C.	
2790	2850	Lime	
2850	2885	Lime	
2885	2987	Lime	
2987	3038	Lime	
3038	3114	Lime	
3114	3225	Lime	
3225	3313	Lime Shale	
3313	3350	Lime	
3350	3360	Lime	
3360	3369	Lime	
3369	3417	Lime	
3417	3465	Lime	
3465	3490	Lime	
3490	T.D.		

I hereby certify the above and foregoing to be a true and correct copy of the log of Petz #1, located in the NW, NW, NW, Sec. 8-21-5W, McPherson County, Kansas to the best of my knowledge.

Correct Attest:

TARGET DRILLING AND PRODUCING CO., INC.

By *R. Schmeier*  
 Secretary

Subscribed and sworn to before me this 12<sup>th</sup> day of March, 1958.

*Esther M. Marshall*  
 Notary Public

My Commission Expires Sept. 19, 1959.

RECEIVED  
 STATE COMMISSION  
 MAR 22 1958  
 DIVISION

PLUGGING  
 FILE: SEC 8 T 21 R 54  
 BOOK PAGE 88 LINE 23