

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER S-009-15699

LEASE NAME Feltes #2

WELL NUMBER SWDW

SPOT LOCATION SE NW SE

SEC. 8 TWP. 16S RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 7/31/85

Plugging Completed 8/13/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Keener Oil Company

ADDRESS 320 S. Boston, Ste 406, Tulsa, Ok. 74103

PHONE # (918) 587-4154 OPERATORS LICENSE NO. 7062

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3331'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4	2090'	none
				8 5/8	2887'	1519'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 2875' & 8 sacks cement. Shot pipe at 2200', 2030', 2003', 1980', 1944', 1910', 1878', 1842', 1810', 1780', 1742', & 1519'. Pulled 55 joints of 8 5/8. Plugged well with 5 hulls, 50 cement, 15 gel, 50 cement, 5 gel, 1 hull, plug, & 100 sacks 60/40 poz 6% gel 3% c.c.  
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 1985

My Commission expires: \_\_\_\_\_



Irene Hoover  
Notary Public

**J-1Z-37-OVERBAY BROS.**

[illegible]

KIND OF FORMATION	TOP	BOTTOM	KIND OF FORMATION	TOP	BOTTOM
	2907		Perf. w/ 40 shots	3054	3062
	2948		Perf. w/ 48 Kone Shot	3287	3293
le - Black	2950				
	2955				
le - Grey	2960				
	2975				
le - Blue	3030				
	3062				
le - Blue	3063				
	3110				
le Grey	3118				
	3156				
	3160				
	3284				
	3288				

(over)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 20 1955  
CONSERVATION DIVISION  
Wichita Kansas  
Lime  
T. D.  
Base of Ordovician 300-350'  
by 0323' SE 2' 16-12  
Q.L. 1905  
1-16-12  
1862  
42-1862  
450