

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-22,907 0000

LEASE NAME Holder

WELL NUMBER 2

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 13 TWP. 16S RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed 09-21-82

Plugging Commenced 09-11-96

Plugging Completed 09-12-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Curt's Oil Operations

ADDRESS P.O. Box 8, Great Bend, Kansas 67530

PHONE#(316) 792-6252 OPERATORS LICENSE No. 4871

Character of Well oil

(oil, gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09-11-96 (date)

by Herb Deines (KCC District Agent's Name).

Is ACC-1 filed? Yes If not, is well log attached? _____

Producing Formation KC-Arbuckle Depth to top 3178 Bottom 3132 r.c. 3400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	357	
	Production			4 1/2"	4396	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Bottom plug; sanded off to 3128' 4 sks of cement. Ran 4 1/2" @ 1400' spotted 65 sks with 200 lbs. hulls. Pulled to 800'. Spotted 30 sks w/150 lbs. hulls. Pulled to 350' cement w/30 sks 150 lbs. hulls. Pulled 150'. Circulated cement w/30 sks. 150 lbs. hulls. Pulled to 150' Circulated cement w/35 sks.

Name of Plugging Contractor D.S.& W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES Curt's Oil Operations

STATE OF Kansas COUNTY OF Barton, ss.

Joseph F. Strube (Employer of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph F. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1996


09-19-96

Harlyn Beck
Notary Public

92:11 V 61 DES 9561

My Commission Expires: 09-28-98.

USE ONLY ONE SIDE OF EACH FORM



Form 05-4
Revised 05-88