


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-009-15765-0000
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Harton County, Sec. 13 Twp. 16S Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines S/2 NW/4
Lease Owner Phillips Pet. Co.-Morton Specter
Lease Name Weber Well No. 2
Office Address Great Bend-Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed March 1947
Application for plugging filed August 21 1954
Application for plugging approved August 24 1954
Plugging commenced Sept. 2, 1954
Plugging completed Sept. 7 1954
Reason for abandonment of well or producing formation not commercially profitable

If a producing well is abandoned, date of last production ~~some time in~~ May 1954
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation Arbuckle Depth to top 3320' Bottom 3328' Total Depth of Well 3328' Feet
Show depth and thickness of all water, oil and gas formations. 5 1/2" casing perforated 3234-38'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8 5/8" OD				494'	None
	5 1/2" OD			5/8"-1 1/2"	3328'	2393'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3255 to 3225 ft.	Sand Bridge
3225 to 3195 ft.	5 sacks cement
3195 to 250 ft.	Mudded
250 to 240 ft.	Rock bridge
240 to 180 ft.	20 sacks cement
180 to 35 ft.	Mud
35 ft. to cellar	10 sacks cement

09-25-54
STATE OF KANSAS
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Ray Ash (If additional description is necessary, use BACK of this sheet)
Address 151 Linwood, Kansas

STATE OF Kansas COUNTY OF ~~Dickinson~~ Russell, ss.
Morton Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morton Specter

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 1954

My commission expires March 9, 1958
W. N. Dawson Notary Public.

PLUGGING
FILE SEC 13 T 16 R 24
BOOK PAGE 68 LINE 23

EXPLORATION RECORD

Lease Weber

Well 2

Formation Name	Top	Base	Remarks
Shale	0	305	
Lime	305	500	
Shale, shells, and salt	500	906	
Shale and lime	906	1614	
Lime	1614	2146	
Shale and shells	2146	2542	
Shale and lime	2542	2796	
Lime	2796	3335	
<u>FORMATION TOPS:</u>			
Kansas City	3046		
Arbuckle	3328		

PLUGGING RECEIVED
 OIL FIELD COMMISSION
 FILE NO. 13 T 10 R 12
 BOOK PAGE 51 LINE 23
 SEP 21 1954