


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-009-15758-0000

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 13 Twp. 16 Rge. 12 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SW NE
Lease Owner Maygill Petr Inc., et al
Sierra Petr Co., Inc.
Lease Name DOLECHECK C Well No. *6
Office Address 202 Oil Exchg Bldg., Calgary Alta., Canada
420 W. Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Was producing oil
Date well completed 5/27/48 19
Application for plugging filed 8/1/56 19
Application for plugging approved 8/2/56 19
Plugging commenced 8/3/56 19
Plugging completed 9/1/56 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Had been temporarily abandoned
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3323 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	224	none
				5 1/2	3322	1714

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Plugged back with crushed rock to 3312' dumped 5 sax cement with dump bailer. Top of cement, 3280'. Pumped in 15 sax of Gel-Mud @ 700' by Sun Cem. Co., Pumped in 75 sax cement @ 313' by Sun Cem. Co., top of cement 20'. Set rock bridge, dumped 5 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
S. P. Hall (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 19 56

Margie Cooper

Notary Public.

My commission expires 1-30-57

PLUGGING
FILE SEC 13 T 16 R 12W
BOOK PAGE 86 LINE 9

09-07-56

Magill Petroleum Co., Inc. et al
DOLECHECK C #6

SE SW NE 13-16-12W
Barton County, Kansas

Total Depth: 3323

Elev: 1890' DF

Comm:
Comp: 5/27/48

Casing
8 5/8" @224'
5 1/2" @ 3322'

Cement
150 sacks cement

Top Anyhdrite 730'

Top Kansas City 3049 (-1159)

3078-84 Limestone white, soft, oolitic with fair porosity and a trace having light stain.

3136-66 Limestone white, soft, oolitic, good porosity and no saturation.

(The zones in Kansas City do not appear to be worth testing.)

Base Kansas City 3293 (-14030)

Top Gorham Sand 3321 (-1431)

3321-23 Sand, soft, finely grained, poor porosity with light saturation.†

Total Depth Rotary 3323.

NO CORRECTION MADE FOR ROTARY MEASUREMENTS

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hall

Subscribed and sworn to before me this 31st day of July, 1956.

Leroy Dietz
Notary Public

My commission expires: 10-17-59

RECEIVED
STATE OF KANSAS
AUG 1 1956
COMMERCIAL

PLUGGING
FILE SEC 13 T 16 R 12W
BOOK PAGE 86 LINE 9