


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-009-07254-0080
WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County, Sec. 13 Twp. 16S Rge. 12 (E) (W)
Location as "NE/CNW&SW" or footage from lines NWc NW/4 NE/4
Lease Owner Sierra Petroleum Co., Inc.
Lease Name Dolecheck "C" Well No. #4
Office Address 420 W. Douglas Ave., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) was producing oil
Date well completed June 9, 1945 19
Application for plugging filed 2/14/57 19
Application for plugging approved 2/15/57 19
Plugging commenced 2/23/57 19
Plugging completed 2/27/57 19
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 1/9/57 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3295 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	236'	none
				5 1/2	3291'	1,899'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Measured into TD 3295'; Plugging started 2/23/57. Finished 2/27/57.
Plugged off bottom with sand back to 3280' and dumped 5 sacks cement with bailer and shot 5 1/2" casing at 1,899'. Pulled pipe out of hole.
Filled hole with mud to 20'. Set rock bridge and mixed 5 sacks cement for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a/ Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
S. P. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall
(Address) _____

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 57

My commission expires 1-30-61.

Margie Cooper
Notary Public.

PLUGGING
FILE SEC 13 T. 16 R. 12W
BOOK PAGE 191 LINE 6

STATE CORP. DIVISION
MAR 14 1957
CONSERVATION DIVISION
Wichita, Kansas
03-14-57

COPY

COPY

COPY

COMPANY: Edwin G. Bradley
CONTRACTOR: Ferrell-Young Drilling Co.
FARM: Dolecheck C #4

LOCATION: NWc NW/4 NE/4
Section 13-16S-12W
Barton County, Kansas

COMMENCED: May 30, 1945
COMPLETED: June 9, 1945
ELEVATION: 1871

CASING RECORD:
8 5/8" 236' 90 sax
5 1/2" 3291' 100 sax

FORMATION	DEPTH
Cellar	4
Shale, Shells & SAnd	236
Shale & Red Rock	700
Anhydrite	725
Shale & Shells	1200
Salt & Shale	1525
Shale & Lime Shells	1680
Lime & Shale Bks.	1825
Lime	1960
Lime & Shale	2100
Shale	2350
Shale & Shells	2560
Shale & Lime	2695
Shale & Shells	2750
Lime	2920
Lime & Shale	3050
Lime	3269
Lime & Shale	3291
Arbuckle Lime	3295
Total Depth	3295

Tops:	Anhydrite	700
	Lansing	3024
	Arbuckle	3295
	Total Depth	3295

I hereby certify this to be a correct and accurate log of the above described well as shown by the drilling reports.

FERRELL-YOUNG DRILLING COMPANY

By: /s/ Leon F. Huff

Subscribed and sworn to before me this 12th day of June, 1945.

/s/ Carmen Reinhardt Leiker

My commission expires: February 19, 1949.

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 13 T 16 R 12 W
BOOK PAGE 141 L E 6