

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40674-00-00

Spot: SESENE Sec/Twnshp/Rge: 36-33S-11E

2894 feet from S Section Line, 276 feet from E Section Line

Lease Name: RANCH (RIGDON-BRUEN FEE Well #: 154

County: CHAUTAUQUA Total Vertical Depth: 1179 feet

Operator License No.: 5970

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD | 7 | 985 | | 2 SX |
| SURF | 10 | 40 | | 10 SX |

Op Name: ELMORE, JOHN A. OR PATRICIA R.

Address: 776 HWY 99
SEDAN, KS 67361

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/15/2017 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: JOHN ELMORE

Company:

Phone: (620) 249-2519

Proposed Run 1" to 985 gel hole spot 20 sacks cement. Pull 1" out perforate at 700' and at 350' Ran 1" to 700' spot 20 sacks cement
Plugging pull up to 350' cement to surface.

Method:

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed: 05/15/2017 12:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1000' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 152 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3

JUN 06 2017

CHANUTE, KS

DS

INVOICED
JUN 22 2017

Remarks: WELL WAS PLUGGED DUE TO COMPLAINECE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed O-A-L

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUN 09 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3