

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23345-00-00
Spot: NENESENW Sec/Twnshp/Rge: 3-8S-21W
1630 feet from N Section Line, 2540 feet from W Section Line
Lease Name: ALEXANDER-THOMAS UNIT Well #: 1-3
County: GRAHAM Total Vertical Depth: 3600 feet

Operator License No.: 32657
Op Name: GATEWAY RESOURCES, LLC
Address: 224 S CRESTWAY
WICHITA, KS 67218

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3572 | | 200 SX |
| SURF | 8.625 | 209 | | 160 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2017 2:30 PM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: GARY F. GENSCHE Company: GATEWAY RESOURCES, LLC Phone: (316) 684-0199

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 400 # hulls and 13 sx gel.
Perforations: 3309' - 3315', 3328' - 3332', 3436' - 3440' and 3449' - 3456'.
Port Collar at 1684' w/150 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2017 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 50 sx cement w/400 # hulls followed by 13 sx gel, followed by 185 sx cement. Topped casing off with 5 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.38967 -099.64960

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3309 | 3315 | | |

Remarks: QUALITY CEMENT TICKET # 240

Plugged through: CSG

District: 04

KCC WICHITA

Signed


(TECHNICIAN)

CM

JUN 02 2017

RECEIVED

MAY 25 2017

Form CP-2/3

INVOICED
JUN 22 2017