

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23276-00-00
Spot: S2SWSWSE Sec/Twship/Rge: 28-21S-13W
100 feet from S Section Line, 2296 feet from E Section Line
Lease Name: RLS Well #: 3
County: STAFFORD Total Vertical Depth: 3807 feet

Operator License No.: 32924
Op Name: GILBERT-STEWART OPERATING LLC
Address: 1801 BROADWAY STE 450
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3600		WITH 2 SX CMT
PROD	5.5	3807	0	WITH 165 SX CMT
SURF	8.625	312		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2017 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: KELLY BRANUM Company: GILBERT-STEWART Phone: (785) 324-1414

Proposed Plugging Method: CIBP @ 3600' WITH 2 SX CMT. PRESSURE CASING. PERFORATE AT 800' & CIRCULATE CMT TO 0'. IF NO CIRCULATION PUMP 50 SX CMT WITH HULLS. PERFORATE AT 350' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2017 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 3600' WITH 2 SX CMT. PRESSURE TESTED CASING TO 300 PSI FOR 5 MINUTES. PERFORATE 5 1/2" CASING AT 800'. ESTABLISH CIRCULATION THROUGH PERFS TO SURFACE WITH FRESH WATER. PUMP CMT TO SURFACE WITH 255 SX CMT. 5 1/2" CASING & ANNULUS WAS STANDING FULL.

Perfs:

Top	Bot	Thru	Comments
3738	3740		

INVOICED
JUN 29 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed *Ken JeHLik*
SA (TECHNICIAN)

RECEIVED
MAY 19 2017
KCC DODGE CITY *MD*