

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21279-00-00
Spot: W2SWSW Sec/Twnshp/Rge: 31-29S-11W
759 feet from S Section Line, 4939 feet from E Section Line
Lease Name: KUMBERG Well #: 2
County: PRATT Total Vertical Depth: 2830 feet

Operator License No.: 8144
Op Name: GUNNER OIL COMPANY
Address: 5201 E 53RD N
KECHI, KS 67067

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2580		
PROD	4.5	2830	0	
SURF	8.625	365		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/13/2017 9:15 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: ALAN VRATIL Company: GUNNER OIL Phone: (620) 886-2419

Proposed Plugging Method: PERFORATE AT 710' & CIRCULATE CMT TO SURFACE. USE 7 SX GEL AHEAD.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2017 10:00 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 2580' WITH 2 SX CMT ON TOP. PERFORATE AT 710'. BREAK CIRCULATION WITH WATER. PUMP 7 SX GEL & 200 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2630	2632		


INVOICED
JUN 22 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed _____


(TECHNICIAN)

RECEIVED
JUN 15 2017
KCC DODGE CITY