

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23911-00-00
Spot: NESWSWE Sec/Twnshp/Rge: 3-9S-19W
423 feet from S Section Line, 2306 feet from E Section Line
Lease Name: ROSTOCIL 'B' Well #: 1
County: ROOKS Total Vertical Depth: 3580 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3578		395 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/28/2017 8:00 AM
Plug Co. License No.: 8914 Plug Co. Name: H & C OIL OPERATING INC.
Proposal Rcvd. from: BOB PLANTE Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Port Collar @1452' -circulated w/215 sx cement. Quality #4447
Ordered 300 sx 60/40 pozmix 4% gel cement, 18 sx gel and 500 # hulls.
LKC perforations: 3246' - 3414' (squeezed).
Production perforations: 3502' - 3534'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/28/2017 10:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3496' and pumped 18 sx gel followed by 25 sx cement w/100 # hulls. Pulled tubing to 1502' and pumped 150 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Shut in pressure 300 psi.

GPS: 39.29385N -099.42699W

Perfs:

Top	Bot	Thru	Comments
3530	3534		
3502	3510		
3412	3414		
3246	3248		

INVOICED
JUN 22 2017

Remarks: QUALITY OILWELL CEMENTING TICKET #215

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

cm

KCC WICHITA

JUN 02 2017

RECEIVED