

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24828-00-00
Spot: NESWNENE Sec/Twnshp/Rge: 16-17S-14W
757 feet from N Section Line, 674 feet from E Section Line
Lease Name: LINSNER A Well #: 1
County: BARTON Total Vertical Depth: 3455 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3454		150 SX
SURF	8.625	807		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2017 10:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: MITCH DRISCOLL Company: H & D EXPLORATION LLC Phone: (620) 653-4791

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2017 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 350' and 1450'. Ran tubing to 3300' and pumped 125 sx cement w/100 # hulls.
Pulled tubing to 1600' and pumped 100 sx cement w/100 # hulls. Had colored water circulating
out braden head. POOH. Hooked to 4 1/2" casing and pumped 80 sx cement. Circulated
cement out braden head and shut in well with 150 psi.

GPS: 38.57731 -098.86956

Perfs:

Top	Bot	Thru	Comments
3402	3405		
3400	3410		

INVOICED
JUN 22 2017

Remarks: QUALITY CEMENTING TICKET # 0177

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JUN 16 2017

CONSERVATION DIVISION
WICHITA, KS