

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-01320-00-00

Spot: SWSNW

Sec/Twnshp/Rge: 17-28S-17E

2178 feet from N Section Line, 1884 feet from W Section Line

Lease Name: WIGGANS

Well #: 10

County: WILSON

Total Vertical Depth: 990 feet

Operator License No.: 31751

Op Name: J-V OIL, LLC

Address: PO BOX 151
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	970		50 SX
SURF	8	20		6 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/30/2017 12:00 PM

Plug Co. License No.: 31751

Plug Co. Name: J-V OIL, LLC

Proposal Rcvd. from: VICTOR HOOD

Company: J - V OIL, LLC

Phone: (918) 629-1776

Proposed Plugging Method: Run one inch pipe inside and outside 2" pipe to fill to surface with Portland cement

Plugging Proposal Received By: ALAN DUNNING

WitnessType: PARTIAL

Date/Time Plugging Completed: 05/30/2017 2:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A one inch cement string was run inside the two inch production pipe to 980 ft. A one inch cement string was also run outside the 2 inch production pipe to 530 ft. The well was then pumped full of cement from btm to top thru these cement strings. A total of 150 sacks of portland cement were used to plug well.

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)

RECEIVED
KCC DIST #3
JUN 14 2017
CHANUTE, KS

AD
INVOICED
JUN 22 2017