

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-21502-00-00  
Spot: E2SENWSE Sec/Twnshp/Rge: 21-32S-14W  
1650 feet from S Section Line, 1470 feet from E Section Line  
Lease Name: HOAGLAND Well #: 1-21  
County: BARBER Total Vertical Depth: 4840 feet

Operator License No.: 32055  
Op Name: JACOBS, GARY D.  
Address: 1957 NW US 281 HWY  
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4640		WITH 2 SX CMT
COND	13.375	70		WITH 54 SX CMT
PROD	4.5	4819	2400	WITH 175 SX CMT
SURF	8.625	1010		WITH 450 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2017 2:30 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4652' WITH 2 SX CMT. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 06/07/2017 3:35 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4640' WITH 2 SX CMT. 1ST PLUG AT 1056' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 352' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 35 SX CMT

Perfs:

Top	Bot	Thru	Comments
4702	4712		


INVOICED  
JUN 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed

  
SA (TECHNICIAN)

RECEIVED  
JUN 15 2017  
KCC DODGE CITY