

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-23526-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 26-13S-20W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: KRAUS B Well #: 3
County: ELLIS Total Vertical Depth: 3880 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 183RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3880		150 SX
SURF	8.625	286		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2017 2:00 PM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: TIM Company: JASON OIL COMPANY Phone: (785) 483-4204

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 3833' - 3835'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2017 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 280', 780', 1550' and 2100'. Ran tubing to 3810' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2865' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1973' and pumped 200 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 30 sx cement. Backside full of cement.

GPS: 38.88600 -099.52029


Perfs:

Remarks: QUALITY CEMENT TICKET # 1560

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

cm

Received
KANSAS CORPORATION COMMISSION

JUN 16 2017

CONSERVATION DIVISION
WICHITA, KS

JUN 13 2017

INVOICED
JUN 22 2017