

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-087-20401-00-00
Spot: SENESE Sec/Twnshp/Rge: 7-10S-20E
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: SEAVER Well #: 2
County: JEFFERSON Total Vertical Depth: 1595 feet

Operator License No.: 3133
Op Name: KLM EXPLORATION COMPANY, INC.
Address: 600 E LAKE PO BOX 151
MCLOUTH, KS 66054

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4	155		160 SX
SURF	8	304		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/21/2017 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: LARRY CULBERTSON Company: KLM EXPLORATION COMPANY, I Phone: (913) 796-6763

Proposed Plugging Method: SPOT PLUGS

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 02/21/2017 9:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:
MIXED AND PUMPED GEL DOWN THE CASING TO KILL GAS. THE 2" TUBING WAS RUN DOWN TO 1550'. PUMPED 30 SACKS OF CEMENT THROUGH THE TUBING AT 1550'. PULLED THE TUBING TO 800' AND PUMPED 15 SACKS OF CEMENT. PULLED THE TUBING UP TO 350' AND CIRCULATED 30 SACKS OF CEMENT TO THE SURFACE. PULLED THE TUBING OUT AND TOPPED THE CASING OFF WITH 16 SACKS OF CEMENT.

Perfs:
RECEIVED
KCC DIST # 3
MAY 30 2017
CHANUTE, KS
TH
INVOICED
JUN 22 2017

Remarks:
Plugged through: TBG

District: 03 Signed Taylor Herman (TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

JUN 02 2017
CONSERVATION DIVISION
WICHITA, KS
6-2-17