

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-20172-00-00  
Spot: SE Sec/Twnshp/Rgc: 13-20S-34W  
1282 feet from S Section Line, 1309 feet from E Section Line  
Lease Name: RHODA CRIST A Well #: 1  
County: SCOTT Total Vertical Depth: 4900 feet

Operator License No.: 3045  
Op Name: LANG, KENNETH R.  
Address: 301 W BELLEVUE  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		
DVT		2660		WITH 300 SX CMT
PROD	4.5	4810	0	WITH 150 SX CMT
SURF	8.625	394		WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2017 8:30 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: KENNETH LANG Company: KENNETH LANG Phone: (620) 640-8218

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/13/2017 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF ROD FISH @ 1525'. TOP OF TBG FISH AT 1212'. SET CIBP @ 1200'. LOAD CASING WITH WATER. RUN CBL FROM 1180' TO 10'. FOUND TOC BEHIND THE 4 1/2" CASING AT 750'. TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 430'. RUN TBG TO 1150' & SPOT 50 SX CMT UP TO 450'. LAY DOWN TBG. PUMP CMT DOWN THE 4 1/2" CASING THROUGH PERFS AT 430' & CIRCULATE TO SURFACE UP THE 4 1/2" X 8 5/8" ANNULUS USING 125 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2631	2641		


INVOICED  
JUN 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

  
SA (TECHNICIAN)

RECEIVED  
JUN 14 2017  
KCC DODGE CITY

