

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-00572-00-00
Spot: NE Sec/Twnshp/Rge: 31-34S-36W
3938 feet from S Section Line, 1278 feet from E Section Line
Lease Name: PARKER ESTATE Well #: 2
County: STEVENS Total Vertical Depth: 2820 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2668	0	WITH 250 SX CMT
SURF	10.75	757		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/09/2017 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2017 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TBG STUCK IN HOLE & RODS PARTED AT 1000'. FISHED ON RODS & TBG FOR 2 DAYS & WAS UNSUCCESSFUL. SHOT TBG AT 1000'. 6/8/17: PUMPED 40 SX CMT WITH 100# HULLS & SHUT DOWN. 6/9/17: TAGGED CMT AT 970' & TESTED CASING TO 500 PSI. HOLDING. PERFORATE AT 800' & PUMP 375 SX CMT WITH NO CIRCULATION BUT GOOD BLOW. 6/12/17: TAGGED CMT IN CASING AT 15', TOP OFF WITH 5 SX CMT. TAGGED CMT ON BACKSIDE AT 64' TOP OFF WITH 80 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2682	2825		

INVOICED
JUN 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed

Kenny Sullivan
518

(TECHNICIAN)

RECEIVED
JUN 13 2017
KCC DODGE CITY