

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-20950-00-00
Spot: NENESWSW Sec/Township/Rge: 30-27S-32W
1217 feet from S Section Line, 4001 feet from E Section Line
Lease Name: EUBANK M H Well #: G2
County: HASKELL Total Vertical Depth: 2865 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2860	0	WITH 600 SX CMT
SURF	8.625	532		WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/25/2017 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CUT TBG AT 1900' & PUMP 100 SX CMT WITH 200# HULLS, WAIT ON CMT & TAG. FILL CASING WITH CMT TO SURFACE FROM TOP OF TAG.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 05/25/2017 6:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

COULD NOT GET TBG FREE AT 1900'. CUT TBG AT 1400'. LAID DOWN ONE JOINT. PUMPED 100 SX CMT WITH 200# HULLS. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 15 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2686	2765		

INVOICED
JUN 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUN 13 2017
KCC DODGE CITY