

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-20817-00-00
Spot: NWNWSESE Sec/Twnshp/Rgc: 16-30S-33W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: HAGUE G U Well #: 2HI
County: HASKELL Total Vertical Depth: 2859 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2859	0	WITH 500 SX CMT
SURF	8.625	620		WITH 330 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/06/2017 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: TBG STUCK IN HOLE. PERFORM FREE POINT TO DETERMINE PLUGGING ORDERS.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 06/06/2017 6:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TBG FREE AT 1100'. SHOT TBG AT 1100'. 1ST PLUG AT 1070' WITH 30 SX CMT & 100# HULLS. 2ND PLUG AT 650' WITH 125 SX CMT TO 0'. CHECK BACKSIDE WITH 5 SX CMT TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
2636	2792		


INVOICED
JUN 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUN 09 2017
KCC DODGE CITY

