

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25400-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 12-16S-15W
590 feet from S Section Line, 640 feet from E Section Line
Lease Name: STRECKER Well #: 1
County: BARTON Total Vertical Depth: 3480 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3476	2360	160 SX
SURF	8.625	448		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/25/2017 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/25/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded back to 2900' and topped off with 5 sx cement. Pulled casing to 1800'. Started flowing. Tied to casing and pumped 50 sx cement. Pulled casing to 1450' and pumped 100 sx cement w/300 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 400' and pumped 40 sx cement w/100 # hulls. Pulled casing to 175' and pumped 30 sx cement. Circulated cement to surface. Pulled casing and hole stayed full.

GPS: 38.66841 -098.92441

Perfs:

Top	Bot	Thru	Comments
3421	3429		
3324	3330		
3306	3310		
3246	3250		
3234	3239		
3196	3200		
3049	3053		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA

JUN 02 2017

RECEIVED

INVOICED
JUN 27 2017