

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-00091-00-02
Spot: NESWNESW Sec/Twushp/Rge: 35-32S-18W
1950 feet from S Section Line, 3324 feet from E Section Line
Lease Name: PEPPERD OWWO Well #: 1-35
County: COMANCHE Total Vertical Depth: 5170 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: PO BOX 1278
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4854		WITH 2 SX CMT
PROD	5.5	5168	3215	WITH 120 SX CMT
SURF	10.75	546		WITH 425 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/07/2017 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY - QUALITY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4854' WITH 2 SX CMT. PLUG AT 1040' WITH 15 SX GEL & 50 SX CMT. PLUG AT 580' WITH 100 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2017 1:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4854' WITH 2 SX CMT. 1ST PLUG AT 1040' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 580' WITH 100 SX CMT. 3RD PLUG AT 260' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 40 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4904	4960		

INVOICED
JUN 27 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed [Signature]
JA (TECHNICIAN)

RECEIVED
JUN 09 2017
KCC DODGE CITY [Signature]