

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20412-00-00
Spot: SWSESESE Sec/Twnshp/Rge: 20-17S-10W
319 feet from S Section Line, 337 feet from E Section Line
Lease Name: HUJING Well #: 1
County: ELLSWORTH Total Vertical Depth: 3305 feet

Operator License No.: 31327
Op Name: PAULEY, GARY DBA PAULEY OIL
Address: 314 5TH ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3290		100 SX
SURF	8.625	252		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/26/2017 11:30 AM
Plug Co. License No.: 6901 Plug.Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GARY PAULEY Company: PAULEY OIL Phone: (785) 252-8024

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 05/26/2017 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPT TO SQUEEZE CASING LEAKS AT 725-800', COULD NOT. PERFORATE AT 1350', 1000', AND 300'. RUN TUBING TO 3240' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING UP TO 1350' AND WAIT 1 HOUR. TAG CEMENT AT 2900'. PUMPED 35 SX'S COMMON WITH 3% CC AT 1350', PULL TUBING TO 750'. WAIT 1 HOUR AND TAG CEMENT AT 950'. PUMPED 35 SX'S COMMON AND 3% CC AT 900', PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3290	3305	OH	

Remarks: WELL HAD TA - N.O.V. SENT ON. GEMINI PERF #3126. COPELAND CEMENT #C-45304.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
JUN 27 2017