

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21142-00-00
Spot: NENENW Sec/Twnshp/Rge: 23-15S-26W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CHAPMAN B (BEARCUB UNIT) Well #: 1-23
County: GOVE Total Vertical Depth: 4400 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4389		500 SX
SURF	8.625	242		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/31/2017 1:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE KERN/BRIAN Company: PINTAIL PETROLEUM, LTD. Phone: (785) 623-3780

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement and 800 # hulls.
Circulated casing with 500 sx cement.
Perforations: 3932' - 3936' and 4320' - 4334'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/31/2017 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4293' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 3293' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 2293' and pumped 75 sx cement. Pulled tubing to 1293' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 25 sx cement. Shut in pressure 200 psi.

GPS: 38.74014 -100.18153

Perfs:

Top	Bot	Thru	Comments
4320	4334		
3932	3936		

Remarks: SWIFT CEMENT TICKET # 30381

Plugged through: TBG

District: 04

Signed: _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 01 2017

JUN 16 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

INVOICED
JUN 27 2017