

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21502-00-00
Spot: S2N2SW Sec/Twnshp/Rge: 22-15S-36W
1660 feet from S Section Line, 1375 feet from W Section Line
Lease Name: SCHROEDER 22C Well #: 1
County: LOGAN Total Vertical Depth: 4973 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237		170 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/26/2017 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: SID Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 05/26/2017 4:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st plug @2600 w/50 sx
2nd plug @1350 w/100 sx
3rd plug @290 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx

Remarks: QEF

Plugged through: DP

INVOICED
JUN 27 2017

District: 04

Signed Richard Williams

(TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

JUN 11 2017

JUN 16 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3