

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-21212-00-00
Spot: NWSWNENW Sec/Twnshp/Rge: 26-2S-26W
780 feet from N Section Line, 1410 feet from W Section Line
Lease Name: BENTON-KISER Well #: 1-26
County: DECATUR Total Vertical Depth: 3874 feet

Operator License No.: 34418
Op Name: PRAIRIE FIRE PETROLEUM, LLC
Address: PO BOX 38
NORTON, KS 67654

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3873		150 sx
SURF	8.625	264		180 SX
T1	2.375	3837		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2017 10:00 AM
Plug Co. License No.: 35469 Plug Co. Name: FRANKS OILFIELD SERVICE, LLC
Proposal Rcvd. from: PRESTON L DREILING Company: PRAIRIE FIRE PETROLEUM, LLC Phone: (785) 639-2099

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations at 3802' to 3805'.
Port Collar at 2103' w/250 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2017 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3800' and pumped 11 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2150' and pumped 220 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 20 sx cement. Backside is full of cement.

GPS: 39.85441 -100.21151

Perfs:


Top	Bot	Thru	Comments
3802	3805		

Remarks: QUALITY CEMENT TICKET # 182

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION
JUN 16 2017
CONSERVATION DIVISION
WICHITA, KS

JUN 13 2017

INVOICED
JUN 27 2017