

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-10008-00-00
Spot: SENWSENE Sec/Twnshp/Rge: 7-32S-38W
1962 feet from N Section Line, 694 feet from E Section Line
Lease Name: YOUNGREN A Well #: 2-7
County: STEVENS Total Vertical Depth: 3016 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3010	0	WITH 225 SX CMT
SURF	8.625	611		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/25/2017 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2017 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CASING LEAK. TBG IS STUCK. ATTEMPT TO CUT TBG AT 1500' & 1200'. WOULD NOT COME. CUT TBG AT 915'. SPOT 25 SX CMT CMT PLUG WITH NO HULLS. RAN TBG. DID NOT TAG. SPOT ANOTHER 25 SX CMT WITH 100# HULLS. SHUT DOWN FOR 2 WEEKS. 5/23/17: TAG TOC IN 4 1/2" CASING AT 853'. PERFORATE AT 640'. INJECTION RATE 4 BPM @ 200#. PUMP 155 SX CMT VIA 4 1/2" CASING THROUGH PERFS WITH PARTIAL RETURNS OUT THE ANNULUS. NO CMT TO SURFACE. WAIT 45 MINUTES. PUMP AN ADDITIONAL 30 SX CMT & CIRCULATED CMT TO SURFACE AT 500# DECREASING TO 300#.

Top	Bot	Thru	Comments
2826	2911		

INVOICED
JUN 22 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
JA

(TECHNICIAN)

RECEIVED
JUN 09 2017
KCC DODGE CITY