

12-13

2 040520

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 159-22,275

Approx.

NW NW NE SEC. 18, T 21 S, R 8 W&E

4854 feet from S section line

2308 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9324

Lease Name V. Altland Well # A-1

Operator: JFW, Inc.

County Rice 118.30

Name & Address RR #1, Box 26

Well Total Depth 3640 feet

Plevna, KS 67568

Conductor Pipe: Size feet.

Surface Casing: Size 8-5/8 feet 205

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling License Number 5107

Address Wichita, KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Mike Tharp

(company name) H-30 Drilling (phone)

were: 35 sx 3600' - 50 sx 1200' - 50 sx 650' - 50 sx 250' - 20 sx 60' -  
10 sx RH - 10 sx WW

RECEIVED  
STATE CORPORATION COMMISSION

DEC 19 1989

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Merlan Unruh  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 09:00 Day: 13 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT Open ended drl pipe was run to 3600' where 35 sx of cmt  
was spotted on the Arbuckle. Drl pipe was pulled to 1200' at salt base where  
50 sx spotted - drl pipe was pulled to 650' at top of salt where 50 sx spotted -  
drl pipe pulled to 250' where 50 sx spotted - pipe pulled to 60' where 20 sx  
cmt was circ to surface. The RH & WW was pulled with 10 sx each. 60/40 poz

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-4-90

Signed [Signature] (TECHNICIAN)

INV. NO. 26890

FEB 09 1990