

5 020176

15-159-06665-0000

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 7-29-64

NW/NE/SE, SEC. 30, T. 21 S, R. 8 (W)E

2310 feet from N(S) section line

2310 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5816

Lease Name Kedley Estate Well # 1

Operator: Gulf Oil Corporation

County Rice 112.13

Name & Address P.O. Box 12116

Well Total Depth 3450 feet

Oklahoma City, OK. 73157

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" BUSHING

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_

STATE CORPORATION COMMISSION  
D&A

Other well as hereinafter indicated \_\_\_\_\_

JUL 10 1985

Plugging Contractor Halliburton Co.

CONSERVATION DIVISION  
License Number \_\_\_\_\_  
Wichita, Kansas

Address Great Bend, Kansas

Company to plug at: Hour: 1:00 PM Day: 3 Month: July Year: 1985

Plugging proposal received from Dan Massingill

(company name) Gulf Oil Corporation (phone) 405 949 7000

were: 7/1/85 Run tubing to 3280' Circulate 7# mud Through Tubing @ 3280' to

cellar. Pump 100 sacks Common Cement through tubing @ 3280'

7/3/85 Run Tubing to 300'. Circulate cement through tubing @ 300' to cellar

Lay down tubing & fill holes (total 60 sacks) Pump 90 sacks Common

Cement into 8 5/8" - 4 1/2" annulus.

Plugging Proposal Received by [Signature]  
TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 PM Day: 3 Month: July Year: 1985

ACTUAL PLUGGING REPORT Run tubing to 3280'. Circulated 7# mud From 3280'

to surface. Pumped 100 sacks Common Cement through tubing @ 3280'

and displaced with 7 bbl mud. Ran tubing to 300'. Circulated cement

to cellar. Layed down tubing and filled 4 1/2" to cellar (total 60 sacks

Common cement.) Pumped 90 sacks common cement into 8 5/8" - 4 1/2"

annulus.

Remarks: Halliburton ticket # 085393

(If additional description is necessary, use BACK of this form.)

INVOICED

(if applicable, this not) observe this plugging:

DATE 7-18-85

Signed [Signature]  
(TECHNICIAN)

INV. NO. 8969

7-3