

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22835-00-00
Spot: SENENWSE **Sec/Twnshp/Rge:** 16-27S-4E
2005 feet from S Section Line, 1449 feet from E Section Line
Lease Name: ML LOOMIS **Well #:** 1
County: BUTLER **Total Vertical Depth:** 2550 feet

Operator License No.:	7228	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name:	<u>BRICKLEY, DONALD DBA D & J INVES</u>	PROD	4.5	2545		6 SX
Address:	<u>107 SE BLUESTEM RD. PO BOX 107</u> <u>EL DORADO, KS 67042</u>	SURF	8.625	202		6 SX

Well Type: OIL **UIC Docket No:** **Date/Time to Plug:** 05/09/2017 8:00 AM
Plug Co. License No.: 99998 **Plug Co. Name:** COMPANY TOOLS
Proposal Rcvd. from: ANDY BRICKLEY **Company:** D & J INVESTMENTS **Phone:** (316) 323-4623

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER **WitnessType:** PARTIAL
Date/Time Plugging Completed: 05/10/2017 5:00 PM **KCC Agent:** DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE & TAGGED TD @ 2535'. SANDED WELL BACK @ 2480', & DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. CUT CASING @ 300', LAYED DOWN 4 1/2" CASING. BAILED WELL @ 250', CMC DUMPED 120 SXS SLURRY MIX TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET # 400046886. 5-10-2017, TAGGED CEMENT @ 30', TOPPED WELL BACK TO SURFACE W/4 SXS. P&A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2545	2550	OH	

INVOICED
JUN 22 2017

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

✓