

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-22869-01-00  
Spot: NWNEENW Sec/Twnshp/Rge: 5-11S-22W  
200 feet from N Section Line, 1981 feet from W Section Line  
Lease Name: FAULKNER Well #: 5 #3H  
County: TREGO Total Vertical Depth: 7966 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	60		100 sx
PROD	7	4476		650 SX
SURF	9.625	334		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/31/2017 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOE Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 470 sx 60/40 pozmix 4% gel cement, 13 sx gel and 300 # hulls.  
CIBP set at 3485'.  
DV Tool at 2327' w/350 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/31/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3483' and pumped 13 sx gel followed by 50 sx cement. Pulled tubing to 2217' and pumped 340 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 25 sx cement. Shut in pressure 300 psi.

GPS: 39.13163 -099.78882

Perfs:

Top	Bot	Thru	Comments
4650	7873		

INVOICED  
JUN 22 2017

Remarks: SWIFT CEMENT TICKET # 30041

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*(Signature)*  
(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

JUN 01 2017

JUN 16 2017

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3